

NorthCentralMechanical.com

CHILLED WATER SYSTEM PHASE I & II

Ft. Stewart, GA









PROJECT DESCRIPTION

Turnkey subcontract to ITSI to install base wide 93,000 linear feet of direct bury pre-insulated welded chilled water pipe in phases.

THE WORK INCLUDED

- -Branch lines to 90 building mechanical rooms and renovation to same
- Modify existing Central Energy Plant piping to keep existing chilled water system operational while new system was being installed
- NDE- Radiography on pipe welds
- Restoration, including sidewalk replacement, paving, curb and gutter and landscaping disturbed during installation of new system

CLIENT

United States Corp of Engineers Savannah District

OWNER

US Army

GENERAL CONTRACTOR

Innovative Technical Solutions, Inc.

CONTRACT VALUE

\$22.9 million

ENGINEER

Hussey, Gay, Bell & DeYoung Inc.

SCHEDULE

November 2008 – December 2010